



- PLAN NOTES
- 1 Shelf and pole
 - 2 Ref. space Refer to specs.
 - 3 Range/oven Refer to specs.
 - 4 Double sink Refer to plumbing schedule #4 Sht. A-5.
 - 5 Water heater Refer to plumbing schedule #6 Sht. A-5.
 - 6 22" x 30" attic access
 - 7 Smoke detector
 - 8 Door chimes
 - 9 Electrical panel board

- ARCHITECTURAL SYMBOLS
- Window symbol
 - Optional window symbol
 - Door symbol
 - INTERIOR ELEVATION INDICATION
 - Room number
 - Finish number (refer to sht. A-6)
 - P.H. Paper holder
 - T.B. Towel bar
 - D.T. Drapery track
 - M# MC Mirror & medicine cabinet
 - FAU Forced air unit
 - C.R. Curtain rod @ tub/shower

AREA TABULATION
GROSS - 828.5 sf
NET - 787 sf

- MECHANICAL SYMBOLS
- Hose bib
 - Vent through roof
 - Vent Pipe
 - Waste line
 - Water heater
 - Clean out
 - Gas outlet
 - Plumbing fixture no. (see sched. sht.A-6)
 - Return air grille
 - Ceiling supply register
 - Wall supply register
 - Combustion air
 - Cubic feet per minute

- ELECTRICAL SYMBOLS
- Ceiling mounted light fixture
 - Wall mounted light fixture
 - Exhaust fan (minimum 5 air changes/hr.)
 - Duplex receptacle, 1 outlet switched
 - Waterproof duplex receptacle
 - Switch
 - 3-way switch
 - Electrical panel brd.
 - Smoke detector
 - Thermostat
 - Duplex receptacle located on a circuit with a ground fault interruptor
 - Prewired cable TV outlet with RG59 cable per cable co.

★RECORD DRWGS.★

FARMERS HOME ADMINISTRATION
All construction performed under the provisions of these plans and specifications shall comply with F.H.A. prescribed standards. Review by F.H.A. of these plans, specifications and related documents does not authorize any violations of F.H.A.'s and other applicable building standards. F.H.A. is not responsible or liable for errors in or omissions from these documents or for deviations from these standards.

Reviewed this 4 day of June 1980
By: *Avelino L. Manotas*
Avelino L. Manotas, F.H.A., Architect

mdw

owner: Thomas A. McLaughlin
contractor: Rural California Housing Systems
San Luis Obispo, Ca. (805) 544-0364

2 bedroom flat

rolling hills apartments

templeton, ca.
S3 unit apartment development

job title:

These plans and specifications are instruments of service prepared for contract construction work and shall be used only under specific agreement with the architect
© mdw 1979

dates:
12/13/79 PLAN CHECK
12/13/79 F.H.A. PLAN CHECK
2/15/80 F.H.A. PLAN CHECK

checked: _____
approved: _____
issued: _____

BRUCE FRASER
project manager

JMP
drawn by

Avelino L. Manotas
signed CG524

job no. 7807

sheet **A-2**
8 of 25 sheets